

# OVALYN UNIVERSAL ACCESS™ UNDER COUNTER SINK

VITREOUS CHINA

# BARRIER FREE

#### **OVALYN UNIVERSAL ACCESS SINK**

- · Vitreous china
- Unglazed rim for under counter mount
- Rear overflow
- · Supplied with template and mounting kit

## 9482.000

#### **Nominal Dimensions:**

19-1/4" x 15-3/4" (489 x 400mm)

#### **Bowl sizes:**

16-3/4" (425mm) wide, 13-1/4" (337mm) front to back, 5-1/2" (140mm) deep 4" (102mm) bowl depth

### Compliance Certifications -Meets or Exceeds the Following Specifications:

- ASME A112.19.2M for Vitreous China Fixtures
- CAN/CSA B45 series
- 1995 National Building Code, section 3.7 and CAN/CSA-B651-M90 and OBC 3.7




● Countertop 864mm (34") from finished floor. Lavatory installed 51mm (2") MIN. from front edge of countertop. Countertop thickness to be 25mm (1") maximum. MEETS THE AMERICAN DISABILITIES ACT GUIDELINES AND ANSI A117.1 ACCESSIBLE AND USEABLE BUILDINGS AND FACILITIES - CHECK LOCAL CODES.

For Universal Design Options, top of counter may be mounted at 813mm (32") minimum from finished floor to meet ADA and ANSI A117.1 requirements. A 838mm (33") minimum mounting height is required for Ontario. Check local codes for heights and faucet handles requirements.



<sup>\*</sup> See faucet section for additional models available





#### NOTES:

FOR COUNTERTOP CUTOUT AND INSTALLATION INSTRUCTIONS USE TEMPLATE SUPPLIED WITH SINK.

FAUCETS NOT INCLUDED AND MUST BE ORDERED SEPARATELY.

\* DIMENSIONS SHOWN FOR LOCATION OF SUPPLIED AND "P" TRAP ARE SUGGESTED.

▼ UNDERCOUNTER MOUNTING KIT SUPPLIED WITH BASIN.

IMPORTANT: Dimensions of fixtures are nominal and may vary within the range of tolerances established by ANSI Standard A112.19.2.

These measurements are subject to change or cancellation. No responsibility is assumed for use of superseded or voided pages.